

MINIMUM REQUIREMENT



WP/SEA MINIMUM REQUIREMENTS CLEANING DRY BULK TANK



MEMORY JOGGERS

Ensure that the following conditions are met before proceeding. If not met, address on WP/SEA.

- Communicate the **“RIGHT TO STOP WORK AUTHORITY POLICY”** and is exercised by all crewmembers and other personnel that believe something or some condition has changed. The job is to be stopped and accessed before proceeding. The WP/SEA may need to be modified or a new WP/SEA maybe required before starting the work task again.
- Review the scope of work with all crew members to ensure a clear understanding among the crew.
- Make sure all gangways are secure
- Inspect all tools and equipment prior to begin of work
- Make sure all rescue equipment is in working order and all 30min. bottles and 5min packs are filled.
- Tank monitoring in 15 min. intervals.
- Identify muster station on boat or on dock
- Visit Minimum Requirement for Operating a Gapvax HV-56 Truck

MINIMUM REQUIREMENTS

- 1) Verify **All** conditions identified in the “Memory Joggers” section are met (or are not applicable); if **ANY** are not met, **STOP** and add the necessary step to the WP/SEA to ensure the safest method possible.
- 2) Barricade open holes prior to begin of work
- 3) Bring all tools and equipment into the work area.
- 4) Verify that all hoses and equipment are in good working condition.
- 5) Secure all suction hoses with duct tape.
- 6) Make sure all rescue equipment is in working order and on site.
- 7) Ensure confine space permits are completed and posted at work area.
- 8) Perform atmosphere testing before making entry into tanks
- 9) Entry person must have Tyvek suit, harness and full face respirator on prior to entry.
- 10) Perform continuous tank monitoring throughout job.
- 11) Walk entire length of suction hose to verify the system is leak-free.
- 12) Verify that Gapvax Truck is grounded.
- 13) Shutdown suction on Gapvax Truck before disconnecting suction hoses.
- 14) Ensure work area is clean and trash is disposed of in proper containers.
- 15) Return hoses to job trailer.

ENSURE MINIMUM REQUIREMENTS NUMBERS ARE RECORDED ON WP/SEA