

# MINIMUM REQUIREMENT



## WP/SEA MINIMUM REQUIREMENTS Cold Cutting Pipe



### MEMORY JOGGERS

Ensure that the following conditions are met before proceeding. If not met, address on WP/SEA.

- Communicate the **“RIGHT TO STOP WORK AUTHORITY POLICY”** and is exercised by all crewmembers and other personnel that believe something or some condition has changed. The job is to be stopped and accessed before proceeding. The WP/SEA may need to be modified or a new WP/SEA maybe required before starting the work task again.
- Ensure pipe is properly supported.
- Check extension cord(s) for cracks and cuts and take out of service if need be.
- Make sure blade on saw is sharp (before checking blade ensure that saw is not plugged in to power).
- Caution tape cutting area, not allowing anyone near cutting operations.
- Possible equipment damage.

### MINIMUM REQUIREMENTS

- 1) Verify **All** conditions identified in the “Memory Joggers” section are met (or are not applicable); if **ANY** are not met, **STOP** and add the necessary step to the WP/SEA to ensure the safest method possible.
- 2) Route extension cords in such a manner that will not cause tripping hazards.
- 3) Support both pieces, when cut, remain stable and will not fall.
- 4) Measure and mark pipe to desired length.
- 5) Plug in saw and begin cutting on marked line.
- 6) Do not rush saw, allow saw to cut using its own weight.
- 7) When pipe is cut all the way through, release trigger on saw.
- 8) Remove saw and place on the deck, not causing a trip hazard.
- 9) Unplug saw and move piece to be installed to designated area.
- 10) Returned discarded piece to designated area.
- 11) Roll up power cord and replace cord, along with saw, to tool house.
- 12) Surrounding piping should be protected by a guard able of keeping any hand tool from causing damage. Also, LO/TO and additionally bleed the surrounding lines if possible.
- 13) Pick up jacks and remove caution tape.
- 14) Sweep area using controlled sweeping methods and deposit all trash in proper receptacle.
- 15) Continue Steps 3 through 10 until job is complete.

**ENSURE MINIMUM REQUIREMENTS NUMBERS ARE RECORDED ON WP/SEA**