

MINIMUM REQUIREMENT



WP/SEA MINIMUM REQUIREMENTS Installing an ATN Package



MEMORY JOGGERS

Ensure that the following conditions are met before proceeding. If not met, address on WP/SEA.

- Communicate the **“RIGHT TO STOP WORK AUTHORITY POLICY”** and is exercised by all crewmembers and other personnel that believe something or some condition has changed. The job is to be stopped and accessed before proceeding. The WP/SEA may need to be modified or a new WP/SEA maybe required before starting the work task again.
- Ensure a crane lift plan has been filled out. (if crane is to be used)
- Ensure that installer is not alone on a jobsite.
- If traveling by boat, complete Travel by Boat Minimum Requirement.
- If traveling by helicopter, complete Helicopter Safety Minimum Requirement.

MINIMUM REQUIREMENTS

- 1) Verify **All** conditions identified in the “Memory Joggers” section are met (or are not applicable); if **ANY** are not met, **STOP** and add the necessary step to the WP/SEA to ensure the safest method possible.
- 2) Gather tools and parts and pack for safe delivery to jobsite.
- 3) Arrive at jobsite either by boat or by helicopter. (Use appropriate Minimum Requirement for arrival)
- 4) Carry tools and parts to work area watching out for pinch points and body strains. (Use buddy system)
- 5) Install lights and solar panels using proper tools and manufacturers’ recommendations.
- 6) Attach fog horn and battery boxes to deck.
- 7) Run and terminate (hook up) cables to lights and solar panels.
- 8) Install and terminate (hook up) batteries.
- 9) Test the system to see if operational.
- 10) If system not operational, check connections and equipment.
- 11) Clean area of old parts, wiring and anything else that may fall overboard and become an environmental hazard.
- 12) Pack up tools and parts for travel.

ENSURE MINIMUM REQUIREMENTS NUMBERS ARE RECORDED ON WP/SEA